

# Automatic As-built BIM Creation of Precast Concrete Bridge Deck Panels Using Laser Scan Data

Qian Wang<sup>1</sup>, Hoon Sohn<sup>2,\*</sup>, Jack C.P. Cheng<sup>3</sup>

<sup>1</sup>Assistant Professor, Department of Building, School of Design and Environment, National University of Singapore, Singapore. Email: bdgwang@nus.edu.sg

<sup>2</sup>Professor, Department of Civil and Environmental Engineering, Korea Advanced Institute of Science and Technology, Daejeon, South Korea (corresponding author). Email: hoonsohn@kaist.ac.kr

<sup>3</sup>Associate Professor, Department of Civil and Environmental Engineering, The Hong Kong University of Science and Technology, Hong Kong, China. Email: cejcheng@ust.hk

## Abstract

Precast concrete bridge deck panels are commonly used for bridge constructions because they enable faster construction and have less impact on traffic flow. The quality of connections between adjacent precast elements must be ensured to guarantee the overall structural integrity of precast systems. Therefore, the dimensional quality of precast concrete panels should be inspected before they are shipped to construction sites for installation. However, current quality inspection of precast concrete elements mainly relies on manual inspection. Furthermore, the as-built dimensions of precast elements are usually stored in paper sheets or Excel spreadsheets, making it difficult to visualize and manage the as-built dimensions. This study develops a technique to automatically estimate the dimensions of precast concrete bridge deck panels and create as-built building information modeling (BIM) models to store the real dimensions of the panels. First, the proposed technique conducts scan planning to find the optimal scanner locations for scan data acquisition. Then, the scan data of the target panel are acquired and pre-processed to remove noise

23 data and to register multiple scans in a global coordinate system. From the registered scan data,  
24 the as-built geometries of the target panel are estimated. In the last step, an as-built BIM model is  
25 created based on the previously estimated geometries. The proposed technique is validated on a  
26 lab-scale specimen and a full-scale precast concrete bridge deck panel. Experimental results show  
27 that the proposed technique can accurately and efficiently estimate the dimensions of full-scale  
28 precast concrete bridge deck panels with an accuracy of 3 mm and automatically create as-built  
29 BIM models of the panels.

## 30 **Introduction**

31 Precast concrete bridge decks have been adopted in the construction of bridges since 1960s  
32 (Alhassan 2011). Compared to cast-in-place (CIP) construction, precast bridge decks offer the  
33 following three advantages (Hieber et al. 2005). First, the quality of precast bridge decks is superior  
34 because they are produced in a controlled plant environment, which has consistent casting  
35 operations and curing processes. Second, precast bridge decks can reduce construction time by 50%  
36 to 75%, thereby reducing the impact on the traffic flow and the safety hazards to workers. Third,  
37 although precast bridge decks have higher initial costs, the life-cycle costs considering road users  
38 and traffic maintenance costs are significantly below those of CIP decks.

39 A typical precast bridge deck consists of a series of precast bridge deck panels. The short sides  
40 of bridge deck panels are parallel with the traffic flow, also known as the longitudinal side surfaces.  
41 On the other hand, the long sides of bridge deck panels are known as transverse side surfaces. Fig.  
42 1 shows a typical precast concrete bridge deck panel with shear pockets, shear keys, and flat ducts,  
43 which are all needed to connect the panel with a girder or an adjacent panel. Shear pockets are  
44 distributed on the top surface of the panel, serving as panel-to-girder connections. Shear connectors  
45 (e.g., studs) on a girder are inserted into the corresponding shear pockets, and grout is filled in the

46 shear pockets for coupled behavior of the panel and girder. The stud-to-shear-pocket connections  
47 prevent both horizontal and vertical movements between the panel and the girder. Shear keys are  
48 introduced on the transverse side surfaces of panels to prevent relative movements between two  
49 adjacent panels and to transfer vertical loading from one panel to the other. The gaps between two  
50 consecutive panels are also filled with grout for continuous behavior of the panels. Flat ducts are  
51 also introduced on the transverse side surfaces. Post-tension cables pass through the flat ducts, and  
52 the connected panels are subjected to compression when tension is applied to the cables via  
53 hydraulic jacking (Alhassan 2011).

54 To guarantee proper connections between adjacent precast elements, the dimensional quality  
55 of individual precast concrete panels, especially the structural features, must be inspected before  
56 the panels are transported to construction sites for installation. The Precast/Prestressed Concrete  
57 Institute (PCI) has specified a quality control check list for precast concrete bridge units, as shown  
58 in Table 1 (Gutt et al. 2000). The tolerance values used in the quality control check list mostly  
59 vary from 6 mm to 13 mm.

60 Current quality inspection of precast concrete panels mainly relies on manual inspection using  
61 traditional measurement tools. Such manual inspection was proven to be subjective and unreliable.  
62 According to Phares et al. (2004), 32% of the bridge component condition ratings performed by  
63 manual inspection varied for at least two rating points (rating scale: 0-9). In addition, manual  
64 inspection is time-consuming, especially for large size structures. For example, according to Wang  
65 et al. (2017), it took around 40 minutes to manually inspect the positions of 88 rebars installed on  
66 a 12 m long reinforced precast concrete panel, resulting in increased labor cost. Although  
67 electronic survey devices such as total stations and laser range finders (Suo et al. 2014; Koo et al.  
68 2013) can provide faster and more accurate dimension measurements, it is still time-consuming to

69 acquire high-fidelity surveying data for large-scale precast concrete panels. Furthermore, current  
70 practice is to manually store the as-built dimensions of inspected panels in paper sheets or Excel  
71 spreadsheets, making it difficult to visualize and manage the actual dimensions of the panels.

72 In the recent decades, 3D laser scanning and building information modeling (BIM) are  
73 adopted in the construction industry. 3D laser scanning can acquire 3D range measurement data  
74 with high accuracy and a high speed, thereby gaining popularity in various applications including  
75 dimension estimation (Tang et al. 2009; Riveiro et al. 2013; Bosché 2010; Kim et al. 2014a; Wang  
76 et al. 2016a; Wang et al. 2016c; Kim et al. 2016; Wang et al. 2017), surface quality evaluation  
77 (Monserrat and Crosetto 2008; Tang et al. 2010a; Bosché and Guenet 2014; Wang et al. 2016b;  
78 Kim et al. 2014b), and construction progress tracking (El-Omari and Moselhi 2008; Turkan et al.  
79 2012; Kim et al. 2013). On the other hand, BIM, as a technology for the storage, visualization and  
80 management of facility information, has been used throughout the lifecycle of buildings and civil  
81 infrastructures. Research efforts have been also made on automatic creation of as-built BIM from  
82 3D laser scan data of facilities (Brilakis et al. 2010; Pu and Vosselman 2009; Tang et al. 2010b;  
83 Xiong et al. 2013; Arayici 2007).

84 The authors' research group has previously developed techniques for dimension estimations  
85 of precast concrete panels using laser scan data (Kim et al. 2014a; Wang et al. 2016a; Kim et al.  
86 2016). However, the previous techniques have the following limitations. First, only one surface of  
87 the target panel is scanned from a single scanner location for dimension estimation. Cases with  
88 multiple surfaces and multiple scanner locations are not taken into consideration. Second, a prior  
89 as-designed BIM of the panel is required to extract the as-built dimensions of structural features  
90 from laser scan data. This dependency on the prior as-designed BIM limits the applicability of the  
91 previous techniques when the as-designed BIM is not available. Third, the as-built dimensions of

92 the panel are not automatically transferred to BIM, making it difficult to visualize and manage the  
93 actual dimensions of the panel.

94 To overcome the above-mentioned limitations, this study develops an automatic as-built BIM  
95 creation technique for precast concrete bridge deck panels. The developed technique aims to  
96 estimate the as-built dimensions of bridge deck panels and to automatically create an as-built BIM  
97 from the estimated dimensions. The proposed technique first conducts scan planning to determine  
98 the optimal scanner locations that can acquire scan data with the minimum number of scanner  
99 locations, while fulfilling certain criteria. Then, the target panel is scanned from the selected  
100 optimal scanner locations, and the obtained scan data are pre-processed for noise removal and  
101 registration of multiple scans. Next, the as-built geometries of the target panel are extracted from  
102 the registered laser scan data. Particularly, the proposed technique can automatically extract certain  
103 structural features based only on the as-designed dimensions of the corresponding features, but  
104 without the as-designed BIM model of the entire structure. Finally, an as-built BIM model is  
105 automatically created based on the estimated dimensions of the target panel. The uniqueness of the  
106 proposed technique includes (1) the development of a scan planning algorithm that enables  
107 automatic registration of scans, (2) the development of an automatic structural feature extraction  
108 algorithm without corresponding as-designed BIM, and (3) the development of an automatic  
109 algorithm for creating an as-built BIM model of a precast concrete panel from the scan data.

## 110 **Literature Review**

111 This section provides a brief literature review related to scan planning, laser scanning based  
112 quality assessment, and as-built BIM creation from laser scan data.

### 113 ***Scan planning***

114 Scan planning aims to prepare a scanning strategy in advance so that the acquired scan data  
115 can achieve certain requirements and the data acquisition time can be minimized. Several studies  
116 have been reported on the scan planning of buildings and civil infrastructure. Argüelles-Fraga et  
117 al. (2013) presented an algorithm to determine scanning parameters that satisfy prescribed  
118 accuracy while minimizing the scanning time. The focus was scanning of circular cross-section  
119 tunnels. Biswas et al. (2015) automatically generated laser scanning strategies based on a 3D BIM  
120 model of the target facility and the characteristics and specifications of the laser scanner. They  
121 also took into consideration the occlusions among facility components. Zhang et al. (2016)  
122 proposed a rapid scan planning method using the "divide-and-conquer" strategy. The strategy first  
123 clustered target points that need to be scanned and then found the scanner locations for each cluster  
124 individually.

125 However, the existing literature on scan planning fails to consider enough overlap between  
126 scan data, thereby failing to achieve fully automatic registration of multiple scans. In most of the  
127 literature, scan registration is still performed by manually picking common points of two scans,  
128 which is time-consuming when dealing with a large number of scan datasets.

### 129 ***Laser scanning based quality assessment***

130 A couple of studies have applied 3D laser scanning to the dimensional quality assessment of  
131 construction components. For example, Alba et al. (2006) monitored the deformations of a large  
132 concrete dam by comparing laser scan data obtained at different times. Bosché (2010) presented a  
133 dimensional compliance check approach for automatically calculating the as-built dimensions of  
134 steel columns by registering the laser scan data to the 3D CAD models. Kim et al. (2016)  
135 performed dimensional quality assurance of full-scale precast concrete panels based on terrestrial  
136 laser scanning and BIM. Wang et al. (2016a) proposed a technique which inspected the

137 dimensional quality of the side surfaces of precast concrete panels.

138 Research efforts have also been reported on assessing surface conditions of structural  
139 components using laser scan data. Tang et al. (2010a) proposed an evaluation framework to  
140 evaluate the performance of different algorithms and scanners for detecting concrete surface  
141 defects. Kim et al. (2014b) proposed a technique to simultaneously localize and quantify spalling  
142 defects on concrete surfaces from laser scan data. Bosché and Guenet (2014) presented an  
143 approach for automatically applying two different standard flatness control techniques to the laser  
144 scan data and assessing the floor flatness based on prescribed tolerances. Wang et al. (2016b)  
145 reported techniques to automatically inspect the surface flatness and distortion of precast concrete  
146 elements using terrestrial laser scanning.

147 The major limitation of the aforementioned techniques is that the as-designed BIM is often  
148 required to recognize objects from the laser scan data. For example, Wang et al. (2016a) aligned  
149 the laser scan data of a precast concrete panel with the as-designed BIM to find the locations of  
150 shear keys. Here, the as-built objects are assumed to be located close enough to the as-designed  
151 ones after alignment. In reality, the as-designed BIM model may not be available, and, even when  
152 the as-designed BIM is available, the discrepancy between the as-built and as-designed objects can  
153 be significant especially for large scale components. Furthermore, since the previous quality  
154 assessment of precast concrete panels is based only on a single scan, the scan data resolution was  
155 limited and the dimension estimation errors could be large (more than 6 mm) (Kim et al. 2016).

#### 156 ***As-built BIM creation from laser scan data***

157 Because manual creation of BIM from laser scan data is time-consuming and labor-intensive,  
158 researchers have developed techniques to automate the BIM creation process. Here, the main  
159 challenges are (1) the registration of multiple scans, (2) geometric modeling, and (3) object

160 recognition.

161 To generate point cloud data covering all surfaces of a target object, often multiple scans need  
162 to be conducted at different locations. Then, the scan data obtained from different scanner locations  
163 are transformed into a global coordinate system. The most well known method for point cloud  
164 registration is the iterative closest point (ICP) algorithm (Besl and McKay 1992; Chen and  
165 Medioni 1991). The ICP algorithm takes one point cloud as the reference and the other point cloud  
166 is iteratively transformed to approach the reference by minimizing the distances between them.  
167 Many variants of the ICP algorithm are also developed such as the Generalized-ICP algorithm  
168 (Segal et al. 2009). However, the ICP algorithm requires a large overlapping area, and the final  
169 solution depends on the initial starting point. Additional algorithms for automatic registration  
170 based on 3D features have been developed in the computer vision area, such as works by Huber  
171 and Hebert (2003) and Makadia et al. (2006). However, the application of these algorithms to the  
172 construction industry has been limited due to self-similarities and lack of "3D features" of  
173 construction components. Instead, plane-based registration approaches have been proposed  
174 specifically for the construction industry, considering that most surfaces of construction  
175 components are planar (Bosché 2012). For example, Dold and Brenner (2006) searched for  
176 corresponding planar patches in two overlapping scans for the registration of scan data. In many  
177 previous studies (Bosché 2010, Bosché 2012, Turkan et al. 2013), a two-step registration approach,  
178 which consisted of 1) a coarse registration using geometric features (such as corresponding planes)  
179 and 2) a fine registration using the ICP algorithm, is adopted. In this study, considering that  
180 surfaces of precast concrete panels are mostly planar as well, the registration approach containing  
181 a corresponding-plane-based coarse registration and an ICP-based fine registration is adopted.

182 Geometric modeling refers to the process of detecting and modeling certain geometric shapes



183 from scan data. The most common shape in the construction industry is a plane. A number of  
184 algorithms have been adopted to detect planes, including the random sample consensus  
185 (RANSAC) algorithm (Bosché 2012), the Hough transform (Tarsha-Kurdi et al. 2007), and the  
186 region-growing algorithm (Xiong et al. 2013). Besides planar surfaces, cylindrical shapes, which  
187 can represent pipes, columns and conduits, have also been studied (Bosché et al. 2015). In this  
188 study, surfaces of precast concrete panels are mostly planar and the RANSAC algorithm is adopted  
189 to extract planes as it has been proven to be efficient and effective for construction components  
190 (Bosché 2012, Jung et al. 2014, Martínez et al. 2012).

191 Object recognition aims to recognize specific construction components (e.g., wall, roof, and  
192 column) from the detected geometric shapes. Many approaches for automatic object recognition  
193 from 3D point cloud data have been proposed. Johnson et al. (1997) used a spin image to describe  
194 the shape of each CAD model and then each point cloud data was recognized by comparing its  
195 spin image with the spin images of all CAD models. Huber et al. (2004) proposed a parts-based  
196 method for classifying scenes of 3D objects, in which objects were divided into individually  
197 recognizable parts. This approach enabled a more flexible class representation and allowed scenes  
198 in which the query object was significantly occluded. Xiong et al. (2013) applied a machine  
199 learning algorithm such that the algorithm can learn the unique features of different construction  
200 components and contextual relationships among them in order to automatically label planar scan  
201 data segments. Rusu et al. (2008) used functional reasoning for assigning a dataset to an object  
202 class using commonsense knowledge (either hardcoded or acquired through learning) for  
203 household environments. Pu and Vosselman (2009) introduced prior knowledge about different  
204 building components so that these components can be recognized from laser scan data segments.  
205 Valero et al. (2015) combined radio frequency identification (RFID) technology with laser

206 scanning to recognize and model furniture including tables, chairs, and wardrobe-like objects.  
207 Although a large volume of literature is available for the recognition of building components or  
208 indoor scenes from point cloud data for building components or indoor scenes, few literature has  
209 been reported on civil infrastructure components. The geometries of civil infrastructure  
210 components are substantially different from those of building components. For example, a single  
211 bridge component (e.g., a pier, girder, or deck unit) can be much larger and more complex than a  
212 specific building component (e.g., wall, floor, door, etc.), making it difficult to apply the previous  
213 research efforts on building components to civil infrastructure components.

## 214 **Proposed Technique**

215 The proposed automatic as-built BIM creation technique consists of five steps, (1) scan  
216 planning, (2) data acquisition and noise removal, (3) scan registration, (4) geometry extraction,  
217 and (5) as-built BIM creation. The details of each step are illustrated in the following.

### 218 ***Scan Planning***

219 Scan planning aims to find the optimal scanner locations for scanning the target panel. The  
220 optimal scanner locations should minimize the total number of scans while fulfilling the following  
221 five performance criteria.

222 (1) Level of accuracy (LOA), which measures how accurate the laser scan data are. For any  
223 specific point on the target, at least one scan should meet the LOA criterion. Although the  
224 measurement accuracy of a scan point is decided by many factors including the scanner's  
225 measurement model, scanning distance to the object, incident angle of the laser beam, and  
226 reflectivity of the surface (Boehler et al. 2003), the dominant factor in this study was the incident  
227 angle of laser beams. According to Soudarissanane et al. (2009), the measurement accuracy

228 decreases as incident angle increases, especially when incident angle is larger than  $70^\circ$ . As for the  
229 specific laser scanner model used in this study, the ranging accuracy with scanning distance of less  
230 than 25 m and surface reflectivity of higher than 10% is always higher than 1.1 mm (FARO, 2017).  
231 The scanning distance was always less than 20 m in this study considering the scale of the precast  
232 concrete panels, and the surface reflectivity of concrete panel surfaces was higher than 35%.  
233 Therefore, the accuracy was not much affected by the laser scanner model, the scanning distance  
234 nor the reflectivity of the concrete surface. Therefore, to fulfill the criterion of LOA, the incident  
235 angle  $\alpha$  should be kept below a certain threshold value of  $\alpha_t$ .

236 (2) Level of detail (LOD), which measures how detailed the laser scan data are. To satisfy the  
237 LOD criterion, the spatial resolution  $s$  (i.e., spacing between two adjacent scan points) should be  
238 less than a threshold value of  $s_t$ . The spatial resolution  $s$  is decided by the angular resolution of  
239 the laser beams, scanning distance to the object, and incident angle of the laser beam. The  
240 relationship between spatial resolution and these parameters is explained in Figure 3. Note that the  
241 LOA and LOD criteria for a specific point on the target must be fulfilled by the same scan.

242 (3) Enabling full registration. In order to facilitate automatic registration of scans in the further  
243 step, all the scans must be able to be registered based on common planes between scans. Fig. 2  
244 shows an example, where the target panel has four planes ( $P1, P2, P3, P4$ ) to scan and three scans  
245 ( $S1, S2, S3$ ) from different locations are conducted. In case 1,  $S1$  covers  $P1$  and  $P2$ ,  $S2$  covers  $P2$   
246 and  $P4$ , and  $S3$  covers  $P3$  and  $P4$ . Since  $S1$  and  $S2$  have a common plane ( $P2$ ), they can be  
247 registered based on the common plane. Similarly,  $S3$  can also be registered with other two scans  
248 so that all the three scans are successfully registered. On the other hand, case 2 assumes that  $S3$   
249 covers only  $P3$ . In this case,  $S3$  has no common plane with any other scan so that all the three scans  
250 cannot be registered. Note that only the six major planes of a typical cuboid panel are likely to

251 become common planes for registration. The small-size planes of structural features, such as shear  
 252 keys, are not considered here.

253 (4) Scan coverage. Among all candidate scanner locations, a scanner location that can cover  
 254 a large area of the target panel is preferred. As shown in Fig. 3, When a scanner is placed at a  
 255 normal distance of  $d$  from the target panel to get qualified (fulfilling the LOA and LOD criteria)  
 256 scan data for point  $P$ , the incident angle  $\alpha$  and spatial resolution  $s$  must fulfill the following  
 257 equations:

$$\alpha \leq \alpha_t \quad (1)$$

$$s \leq s_t \quad (2)$$

258 where  $\alpha$  and  $s$  are obtained as follows:

$$\alpha = \text{atan} \frac{x}{d} \quad (3)$$

$$s = \frac{w}{\cos \alpha} = \frac{\theta \sqrt{d^2 + x^2}}{d / \sqrt{d^2 + x^2}} = \theta \left( d + \frac{x^2}{d} \right) \quad (4)$$

259 where  $\theta$  is the angular resolution, i.e., the angle difference between two consecutive laser beams .  
 260 From Equations (1)-(4), for a specific  $d$  value, the maximum value of  $x$  (the scan coverage)  
 261 becomes:

$$x_{max} = \min \left( d \tan \alpha_t, \sqrt{d \left( \frac{s_t}{\theta} - d \right)} \right) \quad (5)$$

262 It means that, when a scanner is placed at a normal distance of  $d$  from the target panel, the scan  
 263 coverage, which meets both the LOA and LOD criteria, becomes a circular area with a radius of  
 264  $x_{max}$ .

265 Note that the value of  $d$  is bounded between 0 and  $s_t/\theta$ . Fig. 4 shows the relation between  $d$

266 and  $d \tan \alpha_t$  (straight line) and  $\sqrt{d(\frac{S_t}{\theta} - d)}$  (curve). As  $x_{max}$  is defined as the minimum  
267 between  $d \tan \alpha_t$  and  $\sqrt{d(\frac{S_t}{\theta} - d)}$ , the relation between  $d$  and  $x_{max}$  is shown as solid lines in Fig.  
268 4. It is shown that  $x_{max}$  increases from 0 to a maximum value, denoted as  $X$ , and then decreases  
269 to 0. As for this scan coverage criterion, only scanner locations that can cover a circular area with  
270 the radius of  $X/2$  or larger are considered as feasible scanner locations.

271 (5) Field constraints. When it comes to field applications, the placement of a laser scanner is  
272 constrained by factors including physical space available, flatness of the ground, and ambient  
273 vibration. For example, it is typically advantageous to place the scanner at a high elevation position  
274 so that a large area of the target object can be scanned with minimum number of scans. However,  
275 the laser scanner is usually mounted on a tripod and the height of the tripod can only be adjusted  
276 within a certain range, which limits the height of feasible scanner locations.

277 The optimal scanner locations are selected considering the above-mentioned five criteria. First,  
278 feasible scanner locations are identified based on the scan coverage and field constraint criteria.  
279 Then, the optimal scanner locations are selected among all the feasible scanner locations  
280 considering the LOA, LOD, and enabling full registration criteria. Since it takes a long  
281 computational time to find the optimal scanner locations by exhaustive search among feasible  
282 scanner locations, a greedy algorithm is adopted in this study. The greedy algorithm is an  
283 algorithmic paradigm that follows the problem solving heuristic of making the locally optimal  
284 choice at each stage (Black 2004).

285 The greedy algorithm for finding the optimal scanner locations is illustrated in Fig. 5, and  
286 explained as follows. (1) The algorithm finds the first scanner location as the one that provides  
287 qualified scan data for the largest number of points on the target panel. If multiple candidate

288 scanner locations provide qualified data for the same number of points, the algorithm chooses the  
289 one that covers the largest number of planes. (2) The algorithm continues finding the second  
290 scanner location that provides the largest number of qualified new scan data points from the area  
291 not covered by the first scan, also at least shares one common plane with the previous scans. (3) If  
292 all the five criteria are still not fulfilled, the algorithm continues finding the next scanner location  
293 until all the criteria are fulfilled.

### 294 ***Data Acquisition and Noise Removal***

295 After the optimal scanner locations are obtained through scan planning, the scan data of the  
296 target panel are obtained from the selected scanner locations. The data processing starts with noise  
297 removal, which aims to eliminate noise data including background points and mixed pixels while  
298 retaining valid points representing the target panel. Here, mixed pixels are a type of noise data  
299 which occur when the laser beam is split into two parts and lies on both the target surface and the  
300 background surface, respectively. While both reflected signals from two surfaces are received by  
301 the scanner, the resulting scan point can be anywhere along the line of the laser beam. A DBSCAN  
302 based data classification algorithm developed by Wang et al. (2016a) is adopted in this study for  
303 noise removal. Based on the spatial densities of scan points, the algorithm classifies low density  
304 points (e.g., mixed pixels) as noise data and the valid points with high density as one cluster. Fig.  
305 6 shows an example, where the valid points are grouped together as one cluster, background points  
306 as several clusters in different colors, and mixed pixels as noises. Among all the clusters, the one  
307 closest to the laser scanner is chosen and regarded as the valid points representing the target panel.  
308 Note that mixed pixels do not always have lower densities than valid points. Therefore, it is  
309 possible that some mixed pixels still remain in the dataset while some valid points are removed  
310 occasionally.

## 311 **Scan Registration**

312 Scan registration aims to register multiple scans in a global coordinate system based on the  
313 common planes between scans, as illustrated in the following four steps.

314 (1) Extraction of planes from each scan using the RANSAC algorithm (Fischler and Bolles  
315 1981). RANSAC is an iterative method to estimate parameters of a mathematical model (i.e., plane  
316 model in this step) from a set of observed data containing outliers. For example, the top plane of a  
317 precast concrete panel shown in Fig. 7(b) is successfully extracted from the scan data in Fig. 7(a)  
318 using the RANASC algorithm. When a scan covers more than one surface of the target panel, all  
319 these planes are extracted.

320 (2) Identification of common planes between scans. In the scan planning stage, the following  
321 information is already known: (a) Which scans share the common plane and (b) Which part of the  
322 precast concrete panel (e.g., top plane, long side plane, or short side plane) is the common plane.  
323 Therefore, in this step, we only need to identify which plane is the common plane if one scan  
324 covers more than one plane. For a typical cuboid panel, one scan can at most cover three different  
325 planes (a top plane, a long side plane, and a short side plane), which usually have substantially  
326 different sizes. Thus, if one scan covers more than one plane, the common plane can be identified  
327 based on the sizes of planes.

328 (3) Coarse registration of two scans based on their common plane. First, the centroid of the  
329 common plane is computed from each scan by averaging the coordinates of all data points within  
330 the common plane. Second, three principal axes of the common plane are computed by performing  
331 principal component analysis on the scan data points within the common plan. Third, by aligning  
332 the centroid and principal axes of the common plane from two scans, the two scans are coarsely  
333 registered. For example, two different scans shown in Fig. 7(a) and Fig. 7(c) are registered based

334 on their common plane (i.e., the top plane), and the registered scan data are shown in Fig. 7(d).

335 (4) Fine registration of two scans with a common plane using the iterative closest point (ICP)  
336 algorithm. As shown in Fig. 7(e), distances between the two scans are further reduced after fine  
337 registration, showing a better registration result than coarse registration.

### 338 **Geometry Extraction**

339 This step extracts the as-built geometries of the target panel, including the extraction of  
340 structural features and the extraction of outer boundaries of the panel, as illustrated in the following.

#### 341 **Extraction of Structural Features**

342 Extraction of structural features aims to extract the locations and dimensions of structural  
343 features such as shear pockets, shear keys, and flat ducts, from the laser scan data. Various  
344 techniques are available for detecting a certain shape from 3D scan data or 2D images such as the  
345 RANSAC based shape detection from 3D point cloud (Schnabel et al. 2007) and the template  
346 matching approach for 2D images (Gonzalez 1977). In this study, 3D point cloud data are  
347 transformed into a 2D image and the template matching approach is adopted to detect certain  
348 structural features due to a high computational efficiency in 2D domain analysis.

349 Template matching is a technique commonly used in digital image processing for finding  
350 small parts of an image  $f$  which match a template image  $\omega$  (Gonzalez 1977). At each location  
351  $(x, y)$  of image  $f$ , a sub-image with the same size as the template image  $\omega$  is extracted. Then, the  
352 normalized cross-correlation coefficient  $c(x, y)$  between the sub-image of image  $f$  and the  
353 template image  $\omega$  is calculated as:

354



$$c(x, y) = \frac{\sum_s \sum_t [\omega(s, t) - \bar{\omega}] [f(x + s, y + t) - \bar{f}(x + s, y + t)]}{\sqrt{\sum_s \sum_t [\omega(s, t) - \bar{\omega}]^2 \sum_s \sum_t [f(x + s, y + t) - \bar{f}(x + s, y + t)]^2}} \quad (6)$$

355 where  $\bar{\omega}$  is the average value of  $\omega$  and  $\bar{f}(x + s, y + t)$  is the average value of  $f$  in the sub-image.  
 356 After calculating the cross-correlation coefficient values for each location of image  $f$ , a cross-  
 357 correlation coefficient image is generated, as shown in Fig. 8. A higher cross-correlation  
 358 coefficient value indicates that the corresponding sub-image of image  $f$  matches better with the  
 359 template image  $\omega$ . Thus, the pixel with the highest cross-correlation coefficient value indicates the  
 360 most probable location of the template image in image  $f$ .

361 The developed structural feature extraction technique based on template matching is  
 362 performed in the following five steps.

363 (1) Generation of an image from scan data. First, the 3D laser scan data from a surface is  
 364 transformed into a 2D image. The pixel size of the 2D image is equal to the average spatial  
 365 resolution of the scan data. In Fig. 9, the laser scan data of the top surface of a precast concrete  
 366 panel is projected onto the least-square fitted plane of the top surface and transformed into a 2D  
 367 image. Here, the pixel values corresponding to the surface are assigned to one (white color in Fig.  
 368 9(b)), and the remaining pixel values corresponding to the shear pockets are assigned to zero (black  
 369 color). Note that there are no scan data points within the shear pockets, so this dichotomy decision  
 370 can be made easily.

371 (2) Generation of template image. Based on the as-designed dimensions of the specific  
 372 structural feature to detect, a template image is generated. For example, Fig. 9(c) shows the  
 373 template image representing shear pockets. The black square box in the center represents the shear  
 374 pocket, and the surrounding white boundaries are added simply for better contrast of the template  
 375 edges.

376 (3) Calculation of cross-correlation coefficient image. The cross-correlation coefficient image  
377 between the image representing scan data and the template image is obtained based on Equation  
378 (5) and is shown in Fig. 9(d).

379 (4) Estimation of locations of structural features. Pixels with high cross-correlation  
380 coefficients are selected and assigned with pixel values of one (i.e., in white color), as shown in  
381 Fig. 9(e). Then, these selected pixels are clustered using the region growing clustering technique  
382 (Adams and Bischof 1994) and the center of each cluster is defined as the center location of a  
383 detected structural feature.

384 (5) Corner extraction of structural features. After the center location of a structural feature is  
385 identified from the 2D image, the approximate edge positions of the structural feature are identified  
386 in the corresponding laser scan data. Then, all the edges of the structural feature are estimated from  
387 the laser scan data using the edge line estimation algorithm developed by Wang et al. (2016a), and  
388 the intersection points of the edge lines are defined as the corners of the structural feature, as shown  
389 in Fig. 9(f).

390 Fig. 10 shows another example, in which shear keys on the long side surface of a precast  
391 concrete panel are extracted from the laser scan data shown in Fig. 10(a). The unique characteristic  
392 of shear keys is that they have a depth difference from the plane of the side surface. Note that,  
393 because there are no scan points within flat ducts, shear keys and flat duct can be easily  
394 distinguished. Pixel values corresponding to the flat ducts (without any scan points) are assigned  
395 to zero (black color in Fig. 10(b)). The pixel values of all the other points within the side surface  
396 or the shear keys are linearly varied between 0.5 and 1 in proportion to the depth. Here, the depth  
397 is defined as the average distance of all scan points within the pixel to the least-square fitted plane  
398 of the side surface. Ideally, scan points inside the shear keys have pixel values of 0.5 because they

399 have the smallest depth value, and scan points outside any structural features have grey scale values  
400 of 1 because they have the largest depth value. To locate shear keys, a template image is generated  
401 based on the as-designed dimensions of shear keys, as shown in Fig. 10(c). The center square box  
402 representing the shear key has a pixel value of 0.5, and the outer part has a pixel value of 1. The  
403 cross-correlation coefficient image is obtained as shown in Fig. 10(d), and the locations of two  
404 shear keys are identified in Fig. 10(e). The corners of the shear keys are then extracted in Fig. 10(f)  
405 using the technique developed in Wang et al. (2016a).

### 406 **Extraction of Outer Boundaries**

407 Here, the outer boundaries of the panel are extracted. Although each boundary should be a  
408 straight line for typical precast concrete panels, the as-built boundary may have manufacturing  
409 errors. Therefore, to represent an as-built boundary, a set of boundary points are extracted and the  
410 boundary is represented by simply connecting these boundary points.

411 The outer boundaries of a precast concrete panel can be classified into two types. The first  
412 type of boundaries refer to the intersecting boundary of two surfaces where scan data are available  
413 from both surface, such as the intersecting boundary between the top and the side surfaces shown  
414 in Fig. 11. On the other hand, the second type of boundaries only have scan data available only  
415 from a single surface without any scan data from the other surface. The bottom boundaries of side  
416 surfaces usually belong to the second type, because the bottom surface of a panel is often not  
417 scanned, such as the bottom boundary of the side surface shown in Fig. 12. Two different  
418 approaches are developed for each types as described below.

419 For the first type of boundary, the intersection line between two surfaces (the top and the side  
420 surfaces) is firstly extracted, shown as the dashed line in Fig. 11. Along this line, a set of points  
421 ( $P1, P2...P11, P12$  shown as crossings) are then selected with a certain interval  $q$  (depending on

422 the required precision) as the locations for extracting boundary points. For each specific location  
423 ( $P6$ ), a surface ( $PL1$ ), which is crossing point  $P6$  and perpendicular to both the top and the side  
424 surfaces, is defined to indicate this location. Next, a local plane on the top surface ( $PL2$  shown in  
425 Fig. 11) is extracted as the least-square fitted plane of neighboring scan points on the top surface  
426 within a radius of  $q/2$  around  $P6$ . Similarly, a local plane on the side surface ( $PL3$  shown in Fig.  
427 11) is extracted. Finally, the boundary point at the location  $P6$  is extracted as the intersection point  
428 of the three planes ( $PL1$ ,  $PL2$ , and  $PL3$ ).

429 For the second type of boundary, the boundary points are extracted only from the side surface  
430 as shown in the bottom boundary of the side surface in Fig. 12. The scan data from the side surface  
431 are projected onto the 2D plane obtained by least-square fitting of all the scan data points from the  
432 side surface. The last point in each column (i.e., the point closest to the bottom edge) is extracted  
433 among the data points projected onto the 2D plane, and a line is estimated by least-square fitting  
434 all these points, as shown in the dashed line near the bottom boundary of the side surface in Fig.  
435 12. Along this line, a set of locations ( $P1'$ ,  $P2'$ ... $P11'$ ,  $P12'$  shown as crossings) are selected with  
436 a certain interval  $q'$  (depending on the required precision) as the locations for extracting boundary  
437 points. The boundary point at each specific location is extracted in the following five steps.

438 Step 1: For a given location (location  $P6'$ ), scan data points within a certain rectangular area  
439 surrounding  $P6'$  and also on the fitted 2D plan are first extracted, shown as blue dots (both empty  
440 and filled dots) in the zoom-in subfigure of Fig. 12. Here, the center of the rectangular area is  
441 positioned at Location  $P6'$ .

442 Step 2: From these extracted points, the last point in each column (i.e., the point closest to the  
443 bottom edge) is extracted and denoted as type I edge point (shown as filled blue dots).

444 Step 3: In each column, a type II edge point (shown as grey dots) is virtually created next to

445 the type I edge point, assuming that the distance between two consecutive scan points is identical.

446 Step 4: A local edge line at the location  $P6'$  is estimated as a line maximizing the margins to  
447 type I and II scan points using a support vector machine (SVM) algorithm. A more detailed  
448 explanation of the SVM-based edge line estimation algorithm can be found in Wang et al. (2016a).

449 Step 5: The boundary point at location  $P6'$  is extracted as the center within the local edge line  
450 estimated within the rectangular area.

### 451 ***As-built BIM Creation***

452 After the geometries of the target panel are extracted, an as-built BIM is created to store the  
453 geometries. To facilitate information exchange among different project stakeholders, a neutral  
454 BIM data format, namely Industry Foundation Classes (IFC) (buildingSMART 2016), is adopted.  
455 Specifically, the latest version of IFC, namely IFC4, is used in this study. Since the geometries of  
456 precast concrete panels are complex, the geometry is separated into multiple modules for modeling  
457 and all modules are then combined into a single BIM model, as illustrated in the following three  
458 steps.

459 (1) Define modules. For a typical precast concrete panel, each shear pocket, flat duct, and  
460 shear key is defined as one module. In addition, the panel itself excluding all the above-mentioned  
461 structural features is also defined as a separate module.

462 (2) Model individual modules. Each module is modeled using an instance of the IFC entity  
463 namely *IfcFacetedBrep*. An *IfcFacetedBrep* instance represents a solid as a collection of connected  
464 planar surfaces that delimit the solid from the surrounding non-solid. As shown in Fig. 13, the  
465 *IfcFacetedBrep* instance 1 representing a shear key is composed of six planar surfaces. Similarly,  
466 the *IfcFacetedBrep* instance 2 representing a cuboid panel excluding any structural features is also  
467 composed of six planar surfaces.

468 (3) Combine multiple modules. Two or more modules are combined using an instance of the  
469 IFC entity namely *IfcBooleanResult*. An *IfcBooleanResult* instance represents the result of a  
470 Boolean operation of two objects. Here, Boolean operation can be "union", "intersection", or  
471 "difference". The *IfcBooleanResult* instance shown in Fig. 13 is obtained as the "difference" of the  
472 two *IfcFacetedBrep* instances. The same approach can be used to model complex precast concrete  
473 panels with multiple structural features.

#### 474 **Lab-scale Experimental Validation**

475 To validate the proposed technique, a lab-scale experiment was conducted. As shown in Fig.  
476 14, a lab-scale specimen was manufactured using Styrofoam boards, with dimensions of 800 mm  
477 (length)  $\times$  260 mm (width)  $\times$  100 mm (height). The specimen had four shear pockets on the top  
478 surface with identical dimensions of 70 mm  $\times$  60 mm. On each long side, the specimen had two  
479 shear keys with dimensions of 60 mm  $\times$  60 mm and two flat ducts with dimensions of 60 mm  $\times$   
480 40 mm, respectively. To facilitate further explanations, a local coordinate system was constructed  
481 by taking point O (in Fig. 14) as the origin and taking OA, OB, and OC vectors in Fig. 14 as the  
482 X, Y, and Z axes, respectively.

483 In the scan planning step, the threshold value  $\alpha_t$  for the LOA criterion was set to  $70^\circ$  based  
484 on the study by Biswas et al. (2015), the threshold value  $s_t$  for the LOD criterion was set to 2 mm,  
485 and the angular resolution  $\theta$  was set to  $0.018^\circ$ . All the surfaces except the bottom surface of the  
486 specimen needed to be scanned for as-built BIM creation. Since the scanner was mounted on a  
487 tripod and the tripod height could be adjusted from 0.5 m to 2 m, the height (i.e., Z value) of  
488 feasible scanner locations must be ranged from 0.5 m to 2 m. According to the scan planning result  
489 shown in Fig. 15(a), the optimal scanner locations included three locations, namely S1, S2, and  
490 S3. The locations were (1.2 m, 0.8 m, 1.5 m), (1.2 m, -0.8 m, 0.5 m), and (-0.4 m, 1 m, 0.5 m),

491 respectively. The laser scan data were acquired using a FARO Focus 3D 120 terrestrial laser  
492 scanner, which had a ranging accuracy of  $\pm 2$  mm within a distance of 20 m (FARO 2017). The  
493 scan data obtained from three scans were registered through coarse and fine registrations, as shown  
494 in Fig. 15(b). Afterwards, the as-built geometries of the specimen were extracted from the laser  
495 scan data, including the locations and dimensions of structural features and the outer boundaries  
496 of the specimen, as shown in Fig. 15(c). Last, the as-built BIM was created to represent the  
497 geometries of the specimen, as shown in Fig. 15(d).

498 To examine the accuracy of the proposed technique, the extracted as-built dimensions were  
499 compared to the actual dimensions, which were obtained from manual measurement using  
500 measurement tapes. Dimensions for comparison include the dimensions and locations of shear  
501 pockets, shear keys, and flat ducts, and the length, width and height of the specimen, as shown in  
502 Table 2. The dimensions of a shear pocket include the lengths of four boundaries of the shear  
503 pocket, resulting in a total of 16 dimensions for four shear pockets. The locations of a shear pocket  
504 include the distances from four boundaries of the shear pocket to the corresponding boundary of  
505 the specimen (e.g., the distance from the left boundary of the shear pocket to the left boundary of  
506 the specimen), resulting in a total of 16 locations for four shear pockets. Similarly, the dimensions  
507 and locations of four shear keys and four flat ducts include 16 dimensions, respectively. The length  
508 of the specimen was measured on the top surface at three different locations and on each long side  
509 surface at the center location, including a total of 5 measurements, as shown in Fig. 16. The width  
510 of specimen was measured on the top surface at eight different locations and on each short side  
511 surface at the center location, including a total of 10 measurements, as shown in Fig. 16. The height  
512 of specimen was measured on the each long side surface at eight different locations and on each  
513 short side surface at three different locations, including a total of 22 measurements, as shown in

514 Fig. 16. The numbers of length, width, and height measurements on different surfaces were  
515 determined based on the dimensions of the specimen. Generally, the length, width, and height of  
516 specimen were measured for every 100 mm. For example, since the length of the specimen was  
517 around 800 mm, eight ( $800/100=8$ ) width measurements were conducted on the top surface. In  
518 addition, many locations for measuring the length, width, and height of the specimen were along  
519 the edges of structural features. This was to facilitate the measurement because the edges provided  
520 a baseline when measuring the dimensions.

521 As shown in Table 2, the averaged discrepancy ( $\mu$ ) between the dimensions from the proposed  
522 technique and those from manual measurement was ranged from 0.9 mm to 1.7 mm. The height  
523 of the specimen had the largest average discrepancy (1.7 mm). One possible explanation is that  
524 the bottom boundary of each side surface was estimated only from the scan data of the side surface  
525 because the bottom surface of the specimen was not scanned while all the other dimensions were  
526 estimated as the intersection of two surfaces. 122 (91.7%) out of all 133 measurements had  
527 discrepancies less than 2 mm. Considering that the LOD criterion was set to 2 mm, the proposed  
528 technique provided reasonable dimension estimations.

## 529 **Full-scale Experimental Validation**

530 To further validate the proposed technique, an experiment was conducted on a full-scale  
531 precast concrete bridge deck panel with dimensions of 12,600 mm  $\times$  2,480 mm  $\times$  240 mm, as  
532 shown in Fig. 17(a). The panel had 25 shear pockets with dimensions of 440 mm  $\times$  140 mm on the  
533 top surface. In addition, there were 23 shear keys with dimensions of 140 mm  $\times$  140 mm and 14  
534 flat ducts with dimensions of 130 mm  $\times$  60 mm on each of the long side surfaces.

535 In the scan planning of the full-scale panel, all the settings (e.g., LOA criterion, angular  
536 resolution  $\theta$ , and height of feasible scanner locations) were the same as the lab-scale experiment,



537 except that the threshold value  $s_t$  for the LOD criterion was set to 5 mm considering that the  
538 tolerance value for precast concrete panel dimensions varies from 6 mm to 13 mm. As shown in  
539 Fig. 17 (b), the optimal scanner locations included six locations, denoted as S1, S2, S3, S4, S5,  
540 and S6. The coordinates of these locations are (6 m, -2 m, 2 m), (6 m, 5 m, 2 m), (-2 m, -3 m, 0.5  
541 m), (14 m, -3 m, 0.5 m), (-2 m, 6 m, 0.5 m), and (14 m, 6 m, 0.5 m), respectively. Here, the  
542 coordinate system was constructed by taking the left bottom corner of the panel as the origin and  
543 taking the directions of the length, width, and height of the panel as the X, Y, and Z axes,  
544 respectively, as shown in Fig. 17(a). The scan data were acquired using the same scanner as the  
545 lab-scale experiment and the scan data were registered as shown in Fig. 17(c).

546 The as-built geometries of the precast concrete panel were extracted using the proposed  
547 technique. Fig. 18 illustrates the extraction of shear keys and flat ducts from the laser scan data of  
548 a long side surface. Note that the laser scan data shown in Fig. 18 are only a small part (around 2.6  
549 m out of 12.6 m) of the whole long side surface. The laser scan data were first transformed into a  
550 2D image, where pixels without scan points had black colors (pixel values of 0) and pixels with  
551 scan points were normalized into the range [0.5, 1]. Then, using the specific template images for  
552 shear keys and flat ducts, all the five shear keys and three flat ducts on the side surface were  
553 successfully detected. Based on the extracted geometries, an as-built BIM was created in IFC  
554 format, as shown in Fig. 19.

555 To validate the accuracy of the proposed technique, the extracted as-built dimensions of the  
556 panel from the proposed technique were compared to the actual dimensions, which were obtained  
557 from manual measurement. Similar to the lab-scale specimen, the dimensions used for comparison  
558 include the dimensions and locations of shear pockets, shear keys, and flat ducts, and the length,  
559 width and height of the panel, as shown in Table 3. Since it took too much time to manually

560 measure all the dimensions, the dimensions were randomly sampled for manual measurement. For  
561 shear pockets, 12 out of 25 shear pockets were randomly selected for manually measuring their  
562 dimensions and locations. Similarly, 23 out of 46 shear keys and 14 out of 28 flat ducts were  
563 randomly selected for manual measurement. For the length, width, and height of the panel, a total  
564 of 12, 12, and 20 measurements were taken at different locations, respectively, as illustrated in Fig.  
565 20. Note that the X, Y, and Z axes in Fig. 20 are shown in different scales for better illustrations.

566 As shown in Table 3, the averaged discrepancy ( $\mu$ ) between the dimensions from the proposed  
567 technique and those from manual measurement was ranged from 1.2 mm to 2.8 mm. Among all  
568 the 436 measurements, 402 (92.2%) of them had discrepancies less than 3 mm. Since the tolerance  
569 values for precast concrete panel dimensions mostly range from 6 mm to 13 mm according to  
570 Table 1, the 3 mm accuracy achieved by the proposed technique is sufficient enough to provide  
571 accurate dimension estimations supporting the dimensional quality assessment of precast concrete  
572 panels. Although manual inspection is able to achieve a similar accuracy given that each individual  
573 measurement is accurate, in reality, tedious work involved in manual inspection can make it error-  
574 prone and unreliable.

575 The developed technique not only provides more reliable quality inspection results compared  
576 to manual inspection, but also reduces time and labor costs for quality inspection. In the validation  
577 experiment, scan data acquisition took around 20 minutes and data processing took 4 minutes.  
578 Throughout the whole process, only one worker was needed to set-up the scanner and to run the  
579 program. On the other hand, it took two workers around 45 minutes to manually measure and  
580 record the 436 measurements, even though only sampling dimensions were measured. Note that  
581 two workers were needed because some dimensions were too long to be measured by only one  
582 worker. It is estimated that manually measuring all the dimensions can take two workers more than

583 90 minutes, indicating that the proposed technique can reduce the manpower cost for quality  
584 inspection by 86.7%. Therefore, the results demonstrate that the proposed technique can provide  
585 much more efficient dimension estimation compared to manual measurement.

## 586 **Conclusions**

587 The quality assessment of precast concrete panels has been relying on manual inspection,  
588 which is not only subjective and unreliable, but also time-consuming and labor-intensive. In  
589 addition, the quality assessment results are currently stored in traditional ways such as paper sheets  
590 or Excel spreadsheets, making it difficult to visualize and manage the as-built geometries of panels.  
591 Although previous research efforts have been reported on laser scanning based quality inspection  
592 of precast concrete panels, these efforts focused on only one surface of a panel, were dependent  
593 on the as-designed BIM, and did not store the as-built geometries in a BIM model. To tackle these  
594 limitations, this study proposes a technique for automatic creation of as-built BIM of precast  
595 concrete panels using laser scan data. A fully automatic algorithm is developed to extract the as-  
596 built geometries of precast panels from the laser scan data, which enables more accurate and  
597 efficient geometry extraction and quality assessment. The algorithm is able to estimate the as-built  
598 dimensions for an entire panel and to extract the locations of certain structure features based on  
599 only the as-designed dimensions of the features. Furthermore, the extracted geometries of the panel  
600 are then stored in a BIM model, which facilitates the visualization and management of the as-built  
601 geometries.

602 To validate the proposed technique, experiments on a lab-scale specimen and a full-scale  
603 precast concrete panel were performed. For the full-scale panel, when compared with the  
604 dimensions obtained from manual measurement, 92.2% of the dimensions estimated by the  
605 proposed technique had discrepancies less than 3 mm, which is accurate enough for assessing the

606 dimensional quality of precast concrete panels considering the allowable tolerances (6 mm to 13  
607 mm). Although manual inspection can achieve a similar accuracy given that individual  
608 measurement is accurate, manual inspection results can be unreliable due to tedious works  
609 involved. In addition to accuracy and reliability, the dimension estimation by the proposed  
610 technique took only 24 minutes by a single worker, much less than the time necessary for manual  
611 measurement (90 minutes for two workers). The manpower cost for quality inspection was reduced  
612 by 86.7% using the proposed technique. To conclude, the experiments demonstrate that the  
613 proposed technique can estimate dimensions and create as-built BIM for precast concrete panels  
614 in an accurate and efficient manner.

615 This study still has a few limitations. First, LOA and LOD constraints in the scan planning  
616 step still need manual inputs. Future research is warranted for automatic extraction of such  
617 constraints from construction codes. Second, the scan data acquisition still requires manual  
618 maneuvering of the laser scanner to different locations. Vehicle-borne laser scanning or air-borne  
619 laser scanning can be adopted for further automation of data acquisition. Third, the proposed  
620 technique has been tested only in a controlled environment. On real construction sites, it will be  
621 often challenging to place the scanner at desired locations to ensure certain data quality and to  
622 avoid occlusions. An alternative in the future might be to employ air-borne laser scanner although  
623 the accuracy has much room for improvement at this point.

## 624 **Acknowledgement**

625 This research was supported by a grant (13SCIPA01) from Smart Civil Infrastructure  
626 Research Program funded by Ministry of Land, Infrastructure and Transport (MOLIT) of Korea  
627 Government and the Korea Agency for Infrastructure Technology Advancement (KAIA). The  
628 authors also thank Mr. Seongheum Yoon for his help in conducting experiments.

629 **References**

- 630 Adams, R. and Bischof, L. 1994. Seeded region growing. *IEEE Transactions on Pattern Analysis*  
631 *and Machine Intelligence*, 16, 641-647.
- 632 Alba, M., Fregonese, L., Prandi, F., Scaioni, M. and Valgoi, P. 2006. Structural monitoring of a  
633 large dam by terrestrial laser scanning. *International Archives of Photogrammetry, Remote*  
634 *Sensing and Spatial Information Sciences*, 36, 6.
- 635 Alhassan, M. 2011. State-of-the-Art Report on Full-Depth Precast Concrete Bridge Deck Panels.
- 636 Arayici, Y. 2007. An approach for real world data modelling with the 3D terrestrial laser scanner  
637 for built environment. *Automation in Construction*, 16, 816-829.
- 638 Argüelles-Fraga, R., Ordóñez, C., García-Cortés, S. and Roca-Pardiñas, J. 2013. Measurement  
639 planning for circular cross-section tunnels using terrestrial laser scanning. *Automation in*  
640 *Construction*, 31, 1-9.
- 641 Besl, P. J. and McKay, N. D. Method for registration of 3-D shapes. *Robotics-DL tentative*, 1992.  
642 International Society for Optics and Photonics, 586-606.
- 643 Biswas, H. K., Bosché, F. and Suna, M. Planning for scanning using building information models:  
644 a novel approach with occlusion handling. In *Proceedings of the International Symposium*  
645 *on Automation and Robotics in Construction*, 2015.
- 646 Black, P. E. 2004. *Dictionary of algorithms and data structures*, National Institute of Standards  
647 and Technology Gaithersburg.
- 648 Boehler, W., Vicent, M.B. and Marbs, A., 2003. Investigating laser scanner accuracy. *The*  
649 *International Archives of Photogrammetry, Remote Sensing and Spatial Information*  
650 *Sciences*, 34(Part 5), pp.696-701.
- 651 Bosché, F. 2010. Automated recognition of 3D CAD model objects in laser scans and calculation

652 of as-built dimensions for dimensional compliance control in construction. *Advanced*  
653 *Engineering Informatics*, 24, 107-118.

654 Bosché, F. 2012. Plane-based registration of construction laser scans with 3D/4D building models.  
655 *Advanced Engineering Informatics*, 26, 90-102.

656 Bosché, F., Ahmed, M., Turkan, Y., Haas, C. T. and Haas, R. 2015. The value of integrating Scan-  
657 to-BIM and Scan-vs-BIM techniques for construction monitoring using laser scanning and  
658 BIM: The case of cylindrical MEP components. *Automation in Construction*, 49, 201-213.

659 Bosché, F. and Guenet, E. 2014. Automating surface flatness control using terrestrial laser  
660 scanning and building information models. *Automation in Construction*, 44, 212-226.

661 Brilakis, I., Lourakis, M., Sacks, R., Savarese, S., Christodoulou, S., Teizer, J. and Makhmalbaf,  
662 A. 2010. Toward automated generation of parametric BIMs based on hybrid video and  
663 laser scanning data. *Advanced Engineering Informatics*, 24, 456-465.

664 buildingSMART, 2016. Industry Foundation Classes IFC4 Official Release [Online]. Available:  
665 <http://www.buildingsmart-tech.org/ifc/IFC4/final/html/> [Accessed 7 Jan 2017].

666 Chen, Y. and Medioni, G., 1992. Object modelling by registration of multiple range images. *Image*  
667 *and vision computing*, 10(3), pp.145-155.

668 Dold, C. and Brenner, C. 2006. Registration of terrestrial laser scanning data using planar patches  
669 and image data. *International Archives of Photogrammetry, Remote Sensing and Spatial*  
670 *Information Sciences*, 36, 78-83.

671 El-Omari, S. and Moselhi, O. 2008. Integrating 3D laser scanning and photogrammetry for  
672 progress measurement of construction work. *Automation in Construction*, 18, 1-9.

673 FARO, 2017. *Laser Scanner FARO Focus3D* [Online]. Available: [http://www.faro.com/en-](http://www.faro.com/en-us/products/3d-surveying/faro-focus3d/overview)  
674 [us/products/3d-surveying/faro-focus3d/overview](http://www.faro.com/en-us/products/3d-surveying/faro-focus3d/overview) [Accessed 7 Jan 2017].

675 Fischler, M. A. and Bolles, R. C. 1981. Random sample consensus: a paradigm for model fitting  
676 with applications to image analysis and automated cartography. *Communications of the*  
677 *ACM*, 24, 381-395.

678 Gonzalez, R. C. 1977. Digital image processing. Addison-Wesley.

679 Gutt, T. J., Lanier, M. W., Nijhawan, J., Schneider, J. A. and Wilden, H. 2000. *Tolerance Manual*  
680 *for precast and prestressed concrete construction*, Precast/Prestressed Concrete Institute.

681 Hieber, D. G., Wacker, J. M., Eberhard, M. O. and Stanton, J. F. 2005. State-of-the-art report on  
682 precast concrete systems for rapid construction of bridges. Washington State Department  
683 of Transportation.

684 Huber, D. F. and Hebert, M. 2003. Fully automatic registration of multiple 3D data sets. *Image*  
685 *and Vision Computing*, 21, 637-650.

686 Huber, D., Kapuria, A., Donamukkala, R. and Hebert, M., 2004, June. Parts-based 3d object  
687 classification. In *Computer Vision and Pattern Recognition, 2004. CVPR 2004.*  
688 *Proceedings of the 2004 IEEE Computer Society Conference on* (Vol. 2, pp. II-II). IEEE.

689 Johnson, A.E., Hoffman, R., Osborn, J. and Hebert, M., 1997, May. A system for semi-automatic  
690 modeling of complex environments. In *3-D Digital Imaging and Modeling, 1997.*  
691 *Proceedings., International Conference on Recent Advances in* (pp. 213-220). IEEE.

692 Jung, J., Hong, S., Jeong, S., Kim, S., Cho, H., Hong, S. and Heo, J., 2014. Productive modeling  
693 for development of as-built BIM of existing indoor structures. *Automation in*  
694 *Construction*, 42, pp.68-77.

695 Kim, C., Son, H. and Kim, C. 2013. Automated construction progress measurement using a 4D  
696 building information model and 3D data. *Automation in Construction*, 31, 75-82.

697 Kim, M.-K., Sohn, H. and Chang, C.-C. 2014a. Automated dimensional quality assessment of

698           precast concrete panels using terrestrial laser scanning. *Automation in Construction*, 45,  
699           163-177.

700 Kim, M.-K., Sohn, H. and Chang, C.-C. 2014b. Localization and quantification of concrete  
701           spalling defects using terrestrial laser scanning. *Journal of Computing in Civil Engineering*,  
702           29, 04014086.

703 Kim, M.-K., Wang, Q., Park, J.-W., Cheng, J. C., Sohn, H. and Chang, C.-C. 2016. Automated  
704           dimensional quality assurance of full-scale precast concrete elements using laser scanning  
705           and BIM. *Automation in Construction*, 72, 102-114.

706 Koo, K.-Y., Brownjohn, J., List, D. and Cole, R. 2013. Structural health monitoring of the Tamar  
707           suspension bridge. *Structural Control and Health Monitoring*, 20, 609-625.

708 Makadia, A., Patterson, A. and Daniilidis, K., 2006, June. Fully automatic registration of 3D point  
709           clouds. In *Computer Vision and Pattern Recognition, 2006 IEEE Computer Society*  
710           *Conference on* (Vol. 1, pp. 1297-1304). IEEE.

711 Martínez, J., Soria-Medina, A., Arias, P. and Buffara-Antunes, A.F., 2012. Automatic processing  
712           of terrestrial laser scanning data of building facades. *Automation in Construction*, 22,  
713           pp.298-305.

714 Monserrat, O. and Crosetto, M. 2008. Deformation measurement using terrestrial laser scanning  
715           data and least squares 3D surface matching. *ISPRS Journal of Photogrammetry and Remote*  
716           *Sensing*, 63, 142-154.

717 Phares, B. M., Washer, G. A., Rolander, D. D., Graybeal, B. A. and Moore, M. 2004. Routine  
718           highway bridge inspection condition documentation accuracy and reliability. *Journal of*  
719           *Bridge Engineering*, 9, 403-413.

720 Pu, S. and Vosselman, G. 2009. Knowledge based reconstruction of building models from



721 terrestrial laser scanning data. *ISPRS Journal of Photogrammetry and Remote Sensing*, 64,  
722 575-584.

723 Riveiro, B., González-Jorge, H., Varela, M. and Jauregui, D. 2013. Validation of terrestrial laser  
724 scanning and photogrammetry techniques for the measurement of vertical underclearance  
725 and beam geometry in structural inspection of bridges. *Measurement*, 46, 784-794.

726 Rusu, R.B., Marton, Z.C., Blodow, N., Dolha, M. and Beetz, M., 2008. Towards 3D point cloud  
727 based object maps for household environments. *Robotics and Autonomous Systems*, 56(11),  
728 pp.927-941.

729 Schnabel, R., Wahl, R. and Klein, R., 2007, June. Efficient RANSAC for point-cloud shape  
730 detection. In *Computer graphics forum* (Vol. 26, No. 2, pp. 214-226). Blackwell  
731 Publishing Ltd.

732 Segal, A., Haehnel, D. and Thrun, S., 2009, June. Generalized-ICP. In *Robotics: science and*  
733 *systems* (Vol. 2, No. 4, p. 435).

734 Soudarissanane, S., Lindenbergh, R., Menenti, M. and Teunissen, P.J.G., 2009. Incidence angle  
735 influence on the quality of terrestrial laser scanning points. In *Proceedings ISPRS*  
736 *Workshop Laserscanning 2009, 1-2 Sept 2009, Paris, France*. ISPRS.

737 Suo, J.F., Liu, D.D., Feng, M.P., Sun, L. and Yang, L., 2014. Application of reflectorless total  
738 station in bridge detection and its accuracy analysis. In *Applied Mechanics and*  
739 *Materials* (Vol. 501, pp. 1439-1444). Trans Tech Publications.

740 Tang, P., Akinici, B. and Huber, D. 2009. Quantification of edge loss of laser scanned data at spatial  
741 discontinuities. *Automation in Construction*, 18, 1070-1083.

742 Tang, P., Huber, D. and Akinici, B. 2010a. Characterization of laser scanners and algorithms for  
743 detecting flatness defects on concrete surfaces. *Journal of Computing in Civil Engineering*,

744 25, 31-42.

745 Tang, P., Huber, D., Akinci, B., Lipman, R. and Lytle, A. 2010b. Automatic reconstruction of as-  
746 built building information models from laser-scanned point clouds: A review of related  
747 techniques. *Automation in Construction*, 19, 829-843.

748 Tarsha-Kurdi, F., Landes, T. and Grussenmeyer, P., 2007, September. Hough-transform and  
749 extended ransac algorithms for automatic detection of 3d building roof planes from lidar  
750 data. In *Proceedings of the ISPRS Workshop on Laser Scanning* (Vol. 36, pp. 407-412).

751 Turkan, Y., Bosche, F., Haas, C. T. and Haas, R. 2012. Automated progress tracking using 4D  
752 schedule and 3D sensing technologies. *Automation in Construction*, 22, 414-421.

753 Turkan, Y., Bosché, F., Haas, C.T. and Haas, R., 2013. Tracking secondary and temporary concrete  
754 construction objects using 3D imaging technologies. In *Computing in Civil Engineering*  
755 (2013) (pp. 749-756).

756 Valero, E., Adán, A. and Bosché, F. 2015. Semantic 3D reconstruction of furnished interiors using  
757 laser scanning and RFID technology. *Journal of Computing in Civil Engineering*, 30,  
758 04015053.

759 Wang, Q., Kim, M.-K., Cheng, J. C. and Sohn, H. 2016a. Automated quality assessment of precast  
760 concrete elements with geometry irregularities using terrestrial laser scanning. *Automation*  
761 *in Construction*, 68, 170-182.

762 Wang, Q., Kim, M.-K., Sohn, H. and Cheng, J. C. P. 2016b. Surface flatness and distortion  
763 inspection of precast concrete elements using laser scanning technology. *Smart Structures*  
764 *and Systems*, 18, 601.

765 Wang, Q., Sohn, H. and Cheng, J. C. 2016c. Development of a mixed pixel filter for improved  
766 dimension estimation using AMCW laser scanner. *ISPRS Journal of Photogrammetry and*

767            *Remote Sensing*, 119, 246-258.

768    Wang, Q., Cheng, J.C. and Sohn, H. 2017. Automated Estimation of Reinforced Precast Concrete  
769            Rebar Positions Using Colored Laser Scan Data. *Computer-Aided Civil and Infrastructure*  
770            *Engineering*, 32(9), 787–802.

771    Xiong, X., Adan, A., Akinci, B. and Huber, D. 2013. Automatic creation of semantically rich 3D  
772            building models from laser scanner data. *Automation in Construction*, 31, 325-337.

773    Zhang, C., Kalasapudi, V. S. and Tang, P. 2016. Rapid data quality oriented laser scan planning  
774            for dynamic construction environments. *Advanced Engineering Informatics*, 30, 218-232.

775

776

777

778 **Tables**

779

780 Table 1. Part of the checklist for precast concrete bridge units (Gutt et al. 2000)

Item	Tolerance
Length/width of panel	±6 mm
Depth of panel	+6 mm, -3 mm
Dimensions of structural features (shear pockets, shear keys, ducts)	±6 mm
Locations of structural features (shear pockets, shear keys, ducts)	±6 mm
Strand projection from end	±13 mm
Stirrup project from surface	±13 mm
Longitudinal spacing of stirrups	±25 mm

781

782

783 Table 2. Average difference ( $\mu$ ) between the dimensions estimated by the proposed technique and

784 those from manual measurement for the lab-scale specimen.

Dimension	Description	Number	$\mu$ (mm)
Dimensions of shear pockets	Four boundaries of each shear pocket (4) × the number of shear pockets (4)	16	1.3
Locations of shear pockets	From four boundaries of each shear pocket to the corresponding specimen boundary (4) × the number of shear pockets (4)	16	1.2
Dimensions of shear keys	Four boundaries of each shear key (4) × the number of shear keys (4)	16	0.9

Locations of shear keys	From four boundaries of each shear key to the corresponding specimen boundary (4) × the number of shear keys (4)	16	1.2
Dimensions of flat ducts	Four boundaries of each flat duct (4) × the number of flat ducts (4)	16	0.9
Locations of flat ducts	From four boundaries of each flat duct to the specimen boundaries (4) × the number of flat ducts (4)	16	1.3
Length of specimen	Length measurement on the top surface (3) + length measurement on each long side (1×2)	5	1.0
Width of specimen	Width measurement on the top surface (8) + width measurement on each short side (1×2)	10	1.3
Height of specimen	Height measurement on each long side (8×2) + height measurement on each short side (3×2)	22	1.7

785

786

787 Table 3. Average difference ( $\mu$ ) between the dimensions estimated by the proposed technique and

788 those from manual measurement for the full-scale panel.

<b>Dimension</b>	<b>Description</b>	<b>Number</b>	<b><math>\mu</math> (mm)</b>
Dimensions of shear pockets	Four boundaries of each shear pocket (4) × the number of selected shear pockets (12)	48	2.0
Locations of shear pockets	From four boundaries of each shear pocket to the corresponding panel boundary (4) × the	48	1.6

	number of selected shear pockets (12)		
Dimensions of shear keys	Four boundaries of each shear key (4) × the number of selected shear keys (23)	92	1.2
Locations of shear keys	From four boundaries of each shear key to the corresponding panel boundary (4) × the number of selected shear keys (23)	92	1.7
Dimensions of flat ducts	Four boundaries of each flat duct (4) × the number of selected flat ducts (14)	56	1.5
Locations of flat ducts	From four boundaries of each flat duct to the corresponding panel boundary (4) × the number of selected flat ducts (14)	56	2.0
Length of panel	Length measurement on the top surface (10) + length measurement on each long side (1×2)	12	2.2
Width of panel	Width measurement on the top surface (10) + width measurement on each short side (1×2)	12	1.6
Height of panel	Height measurement on each long side (5×2) + height measurement on each short side (5×2)	20	2.8